## **30,000 lb. Material Cart with Brakes**



- 30,000 lb. work capacity.
- 4 wheel failsafe air brakes.
- 16' X 6' deck with 1/4" diamond plate steel deck.
- 16" forged steel wheels.
- 2 15/16" axles with pillow block bearings.
- 3/4" X 5 1/2" hitch plates both ends.
- Remote grease fittings.
- Stake pockets.



## Sperling Railway Services, Inc.

4313 Southway St. SW Canton, Ohio 44706 Phone: 330-479-2004 Fax: 330-479-2006 E-mail: info@sperlingrailway.com Website: www.sperlingrailway.com